

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: 2-9

Corner common to Sections 32 and 33, T.35S., R.29E., W.M.

The original south township line was run in 1872 by Williams under Contract 176. His record states: Set a stone 24x12x4.

1	DIAGRAM	1
1	R29E	1
1	T3S S32   S33	1
1	T4S S5	1
1	1996	1
1	PLS 852	1

Description of corner evidence found:

Found the original stone laying flat on the ground with clearly visible notches, a Kinzua location poster on a nearby tree, and 20" Ponderosa Pine snag with an old open blaze and visible scribing southeast of the corner. This tree is of unknown origin and does not appear to have been marked by Williams in the original survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the location of the record stone, I set a 30" x 2.25" aluminum pipe with a 2.5" aluminum cap 26" in the ground stamped as shown in the diagram above. I built a mound of stone around the monument.

Marked the following witness trees:


- A 10" Douglas Fir bears N62°48'E, 14.17' scribed T3SR29ES33BT.
- A 10" Western Larch bears S26°59'E, 64.35' scribed T4SR29ESBT.
- A 9" Ponderosa Pine bears S84°52"W, 5.91' scribed T4SR29ESBT.
- A 10" Western Larch bears N25°57'W, 47.13' scribed T3SR29ES32BT.

The distances and bearings are measured to the head of a nail attaching a brass washer stamped ORLS852 and WAL513922 between the letters B and T on each tree.

This work was done October 22, 1996.



*David L. Haddock*



Office of \_\_\_\_\_ County of MORROW

State of OREGON, I hereby certify that the within instrument was filed in this office for record on the 18<sup>th</sup> day of NOVEMBER, 1996.

SKB by \_\_\_\_\_ ( COUNTY OFFICIAL ) ( DEPUTY )