

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

T.4N., R.24E., INDEX N-17


**History of original corner establishment:**

This corner was originally established by John B. David under G.L.O. contract No. 131, dated June 8, 1869. Survey General notes state:

Set stone 15x10x4 for 1/4 sec. corner.

Corner re-established in 1983 by Timberland McCullough, Morrow County Map of Survey C-644-K. Plat states:

"Set BD in grout in running surface of road"



**Description of corner evidence found:**

We recover the brass disk set by Timberland McCullough, Map of Survey C-644-K

**Description of monument and accessories I establish to perpetuate the original location of this corner:**

At the position of the said brass disk, set a 2-1/2" dia. x 30" steel pipe monument w/3" dia. brass cap stamped as shown in the DIAGRAM, 5" below the road grade, in a cast iron monument box, from which:

- A 5/8" iron pin bears N00°04'42"E, 20.00 ft., R/W pin Sta. 31+04.83, 20' Lt.
- A 5/8" iron pin bears N81°49'32"E, 118.84 ft.
- A 5/8" iron pin bears S00°04'42"W, 30.00 ft., R/W pin Sta. 31+04.83, 30' Rt.
- A 5/8" iron pin bears S00°04'42"W, 40.00 ft., R/W pin Sta. 31+04.83, 40' Rt.

**DIAGRAM**

T4N R24E  
S15|S14  
----  
S22|S23  
2009  
PLS 49865

Measurements to accessories taken with Topcon Hyper Lite GPS.

I hereby certify that the above corner point was perpetuated as shown hereon in March, 2009

Witness: D. Mitchell Ferguson, LSIT  
David H. Herburger, Surv. Tech.

Office of County Surveyor \_\_\_\_\_ County of Morrow  
State of Oregon. I hereby certify that the within instrument was filed in this office  
for record on the 16<sup>th</sup> day of April, 2014

Stephen K. Haddock by \_\_\_\_\_  
County Surveyor Deputy

See Morrow County Map of Survey No. 2013-38D(1685)

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 13, 1999  
KENNETH H. DELANO JR.  
49865

RENEWS: 1/1/2016