

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T.4N., R.24E., INDEX N-23


History of original corner establishment:

This corner was originally established by John B. David under G.L.O. contract No. 131, dated June 8, 1869. Survey General notes state:

Set post in mound as per instruction for 1/4 sec cor.

Corner re-monumented by Dennis Edwards in 1993. Referring to Morrow County Map of Survey C-1230-E. Plat states:

"FND 5/8" IRON REBAR WITH 2" ALUM CAP, ME 1993"



Description of corner evidence found:

We recover a 5/8" pin and cap set by Edwards in 1993. Refer to Map of Survey C-1230-E.

Description of monument and accessories I establish to perpetuate the original location of this corner:

At the position of the said 5/8" pin, set a 2-1/2" dia. x 30" steel pipe monument w/3" dia. brass cap stamped as shown in the DIAGRAM, 5" below the road grade, in a cast iron monument box, from which:

An X chiseled in concrete ditch bears N00°54'49"W, 20.00 ft., R/W Sta. 11+04.65, 20' Lt.
A 5/8" iron pin bears S00°54'49"E, 30.00 ft., R/W pin Sta. 11+04.65, 30' Rt.

DIAGRAM

T4N R24E
S13
1/4----
S24
2009
PLS 49865

Measurements to accessories taken with Topcon Hyper Lite GPS.

I hereby certify that the above corner point was perpetuated as shown hereon in March, 2009

Witness: D. Mitchell Ferguson, LSIT
David H. Herburger, Surv. Tech.

Office of County Surveyor _____ County of Morrow
State of Oregon. I hereby certify that the within instrument was filed in this office
for record on the 16th day of April, 2014

Stephen K. Haddock by _____
County Surveyor Deputy

See Morrow County Map of Survey No. 2013-38D(1685)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 13, 1999
KENNETH H. DELANO JR.
49865
RENEWS: 1/1/2016