

OREGON CORNER RESTORATION FORM

SECTION 1 TOWNSHIP 4N RANGE 25 E A-21

COUNTY: UMATILLA DATE 12/92

CORNER DESIGNATION

Northwest Corner.

___CONDITION REPORT ONLY

___NOT FOUND

___RENEWED

___UNRECORDED

SURVEYED IN

REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Maxon and Hurd.
BLM Dependent Resurvey in 1968 by White.
In January 1979 Wengler set a 8" x 30" concrete monument with
a 3" Brass Cap, using BLM's field note ties.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 3" Brass Cap, stamped as below, 1 foot below surface.

MONUMENT DETAIL

SKETCH

LS 1002
TSN R24E

35 36

2 1

T4N R24E
1978

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

An Alum. tag #951 in RR tie fence post Bears. N 25° 11' E
3.22 feet. Attached Bearing Object and Witness Corner signs.
An Alum. tag #951 in Power pole Bears. S 88° 06' W 154.11
feet. Attached Bearing Object sign.
The North face of a 10" P.V.C. valve box Bears. S 3° 41' E
54.88 feet.
An Alum. tag #951 in Power pole Bears. S 89° 05' 30"E 169.78
feet. Attached Bearing Object sign.


LOCATION & COMMENTS

From RR overpass on
Old Oregon Trail Hwy.
go 1.3 miles north-
easterly to a fence
corner. Go West along
fence line 0.5 mile
to Corner.

SURVEYOR'S SEAL

COMPASS DEC.

FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT



G. Dennis Edwards

RECEIVED BY
Morrow County Surveyor

Date 1/26/93

Rec'd By DE

No. _____

