

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT  
Morrow County Surveyor's Office

J-11

<b>SECTION</b> 9 16	<b>TOWNSHIP</b> 4 NORTH	<b>RANGE</b> R 25 E	<b>DATE</b> DECEMBER 12, 2012
<b>COUNTY:</b> Morrow			(Please check one)
<b>CORNER DESIGNATION:</b> The Corner common to Sections 9 and 16, T4N, R25E, W.M., Morrow County, Oregon.			
Previous Renewals / Surveys, etc. See Morrow County Records.			<input type="checkbox"/> Condition Report Only <input type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input type="checkbox"/> Surveyed In <input checked="" type="checkbox"/> Referenced Out
<b>Monument(s) &amp; Accessories Found: (Condition &amp; Source)</b> Found Brass Screw and Washer on 1 1/2" ID pipe, USACE.			
<b>Monument Detail:</b>		<b>Sketch:</b>	
<b>Monument Set (Procedures and Description):</b> Set corner based on Krumbain's 1975 survey for Homer Prichard. Set 2" I.D. x 30" galvanized pipe with a 2 3/8" Brass Cap.			
<b>New Accessories: From which</b> A RR tie fence post with BO sign bears East 8.05 feet. A 7/8" x 24" rebar driven 1 foot below the surface bears South 2.15 feet. A 3/4" x 20" rebar driven 1 foot below the surface bears West 2.0 feet. A T-post with witness and bearing object signs bear North 0.29 feet.			
<b>Location &amp; Comments:</b>		<b>Compass Declination:</b>	
Firm / Agency Copcock Surveying		<b>SURVEYOR'S SEAL</b>	
<b>Address:</b> P.O. Box 495 Heppner, OR. 97836 <b>Party Chief</b> Judson L. Copcock			
<b>Notes</b>			
<b>Witness</b>			

RENEWAL DATE: DEC. 31 / 13