

**OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT**  
Morrow County Surveyor's Office


J-15

<b>SECTION</b> 10 15	<b>TOWNSHIP</b> 4 NORTH	<b>RANGE</b> R 25 E						
<b>COUNTY:</b> Morrow		<b>DATE</b> DECEMBER 12, 2012						
<b>CORNER DESIGNATION:</b> The 1/4 Corner common to Sections 10 and 15, T4N, R25E, W.M., Morrow County, Oregon.								
<table border="0" style="width:100%;"> <tr> <td style="width:15%;"><input type="checkbox"/> Condition Report Only</td> </tr> <tr> <td><input type="checkbox"/> Not Found</td> </tr> <tr> <td><input type="checkbox"/> Renewed</td> </tr> <tr> <td><input type="checkbox"/> Unrecorded</td> </tr> <tr> <td><input checked="" type="checkbox"/> Surveyed In</td> </tr> <tr> <td><input checked="" type="checkbox"/> Referenced Out</td> </tr> </table>			<input type="checkbox"/> Condition Report Only	<input type="checkbox"/> Not Found	<input type="checkbox"/> Renewed	<input type="checkbox"/> Unrecorded	<input checked="" type="checkbox"/> Surveyed In	<input checked="" type="checkbox"/> Referenced Out
<input type="checkbox"/> Condition Report Only								
<input type="checkbox"/> Not Found								
<input type="checkbox"/> Renewed								
<input type="checkbox"/> Unrecorded								
<input checked="" type="checkbox"/> Surveyed In								
<input checked="" type="checkbox"/> Referenced Out								
Previous Renewals / Surveys, etc. See Morrow County Records.								
Monument(s) & Accessories Found: (Condition & Source) No evidence found.								
<b>Monument Detail:</b>  <div style="text-align: center; border: 1px solid black; border-radius: 50%; width: 100px; margin: 0 auto; padding: 10px;"> T4N R25E   1/4 <math>\frac{10}{15}</math>   2006  LS 2850 </div>	<b>Sketch:</b>							
<b>Monument Set (Procedures and Description):</b> Set corner based on Krumbain's 1975 survey for Homer Pritchard. Set 2" I.D. x 30" galvanized pipe with a 2 3/8" Brass Cap.								
<b>New Accessories:</b> From which A RR tie fence post with sign bears East 12.49 feet. A 5/8" rebar bears S 01° 08' 39" 200.05 feet. A T-post with Bearing Object and Witness signs bears West 0.85 feet. A square rod 0.7 x 1.7 buried 1 foot bears South 2.10 feet.								
<b>Location &amp; Comments:</b>		<b>Compass Declination:</b>						
<b>Firm / Agency</b> Coppock Surveying								
<b>Address:</b> P.O. Box 495 Heppner, OR. 97836								
<b>Party Chief</b> Judson L. Coppock								
<b>Notes</b>								
<b>Witness</b>								

**SURVEYOR'S SEAL**



*Judson L. Coppock*



**RENEWAL DATE: DEC. 31/13**