

**OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT**  
Morrow County Surveyor's Office

J-9

<b>SECTION</b>	<b>TOWNSHIP</b> 4 NORTH	<b>RANGE</b> R 25 E						
<b>COUNTY:</b> Morrow		<b>DATE</b> DECEMBER 12, 2012						
<b>CORNER DESIGNATION:</b> The Corner common to Sections 8, 9, 17 and 16, T4N, R25E, W.M., Morrow County, Oregon.								
<table border="0" style="width:100%;"> <tr> <td style="width:15%;"><input type="checkbox"/> Condition Report Only</td> </tr> <tr> <td><input type="checkbox"/> Not Found</td> </tr> <tr> <td><input type="checkbox"/> Renewed</td> </tr> <tr> <td><input type="checkbox"/> Unrecorded</td> </tr> <tr> <td><input type="checkbox"/> Surveyed In</td> </tr> <tr> <td><input checked="" type="checkbox"/> Referenced Out</td> </tr> </table>			<input type="checkbox"/> Condition Report Only	<input type="checkbox"/> Not Found	<input type="checkbox"/> Renewed	<input type="checkbox"/> Unrecorded	<input type="checkbox"/> Surveyed In	<input checked="" type="checkbox"/> Referenced Out
<input type="checkbox"/> Condition Report Only								
<input type="checkbox"/> Not Found								
<input type="checkbox"/> Renewed								
<input type="checkbox"/> Unrecorded								
<input type="checkbox"/> Surveyed In								
<input checked="" type="checkbox"/> Referenced Out								
Previous Renewals / Surveys, etc. See Morrow County Records.								
Monument(s) & Accessories Found: (Condition & Source) Found Brass cap set by BLM in 1975.								
<b>Monument Detail:</b>	<b>Sketch:</b>							
<b>Monument Set (Procedures and Description):</b> Set corner based on Krumbein's 1975 survey for Homer Pritchard. Set 2" I.D. x 30" galvanized pipe with a 2 3/8" Brass Cap.								
<b>New Accessories:</b> From which A Power pole with sign bears N 82°W 56.94 feet. A power pole with sign bears N 83° E 96.27 feet. A USACE Brass screw and washer bears N 68° E 2.80 feet. A T-post with witness and bearing object signs bear North 0.21 feet.								
<b>Location &amp; Comments:</b>		<b>Compass Declination:</b>						
<b>Firm / Agency</b> Coppock Surveying		<b>SURVEYOR'S SEAL</b>						
<b>Address:</b> P.O. Box 495 Heppner, OR. 97836								
<b>Party Chief</b> Judson L. Coppock								
<b>Notes</b>								
<b>Witness</b>		<b>RENEWAL DATE:</b> DEC. 31/13						