

# CORNER RESTORATION FORM

Township 4N Range 25E Section 21 County MORROW

State OREGON Date 2/27/2015 Number N-11

Corner Designation : 1/4 CORNER SEC. 21 & 16

- Condition Report Only
- Not Found
- Renewed
- Surveyed In
- Referenced

Previous Renewals ORIGINAL SOURCE OF CORNER

UNDER GLO CONTRACT #131 BY JOHN DAVIS COMPLETED

OCTOBER 1869 SET POST IN MOUND OF EARTH

---

**Monuments and Accessories Found:**

NONE

---



---




---



---

## MONUMENT DETAIL

Found  Set



### Monument & Accessories Set (Procedure and Description)

- SET 3" ALUMINUM CAP ON 5/8" REBAR 1/2" BELOW PAVEMENT GRADE MARKED AS SHOWN, SET BY RETRACEMENT OF RECORD OF SURVEY C-810-K. BEARINGS ARE BASED ON SURVEY NO. 2015-1727C
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE N83°E 337.87, WITH BEARING OBJECT SIGN, NEAR FENCE LINE.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE N33°W 30.48, NEAR WOOD IRRIGATION BOX.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE S57°E 82.95, NEAR CONCRETE PIVOT BASE.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE S20°W 47.67, WITH BEARING OBJECT SIGN, NEAR CONCRETE IRRIGATION BOX.

### Sketch of Monument, Accessories and General Area

SET 5/8" REBAR & CAP PLS 61420 SET BEARING OBJECT SIGN

SET 3" ALUM CAP ON 5/8" REBAR 1/2" BELOW PAVEMENT

SET 5/8" REBAR & CAP PLS 61420 NEAR WOOD VALVE BOX

SET 5/8" REBAR & CAP PLS 61420 SET BEARING OBJECT SIGN, NEAR CONCRETE VALVE BOX

SET 5/8" REBAR & CAP PLS 61420 NEAR PIVOT BASE

KUNZE LANE

Surveyor's Seal

**REGISTERED PROFESSIONAL LAND SURVEYOR**

*Lance Clark King*

**OREGON**  
MAY 10, 2011  
**LANCE CLARK KING**  
61420

**RENEWS: 6/30/2015**

**Agency:**  
CK3, LLC  
945 W. ORCHARD  
HERMISTON OREGON 97838  
OFFICE: 541-567-2345  
FAX: 541-567-2305  
WEB: CK3LLC.NET  
Field Book # 0-289

---

**COUNTY SURVEYOR RECORDING INFO**

Received 3-16-2015

Filed 3-16-2015

Survey No. 2015-1727C

Drawing No. 1727

Index No. N-11