

CORNER RESTORATION FORM

Township 4N Range 25E Section 21 County MORROW

State OREGON Date 2/27/2015 Number R-13

Corner Designation : SE CORNER SEC. 21

- Condition Report Only
- Not Found
- Renewed
- Surveyed In
- Referenced

Previous Renewals ORIGINAL SOURCE OF CORNER


UNDER GLO CONTRACT #131 BY JOHN DAVIS COMPLETED
OCTOBER 1869 SET POST IN MOUND OF EARTH.
IN MAY OF 1986 SURVEY NO. C-810K SET STANDARD
BERNTSEN MONUMENT.

Accessories Found:

NONE

MONUMENT DETAIL

Found Set



Monument & Accessories Set (Procedure and Description)

- SET 2 1/2" BRASS CAP ON 2"x30" PIPE AT SURFACE MARKED AS SHOWN, SET BY
- RETRACEMENT OF RECORD OF SURVEY C-810-K. BEARINGS ARE BASED ON SURVEY NO. 2015-1727C.
- SET 5/8" REBAR & CAP CK3 LLC AT GRADE N88°W 211.46, NEAR PIVOT WHEEL STOP.
- SET 5/8" REBAR & CAP CK3 LLC AT GRADE N81°E 52.00, NEAR PIVOT WHEEL STOP.
- SET 5/8" REBAR & CAP CK3 LLC AT GRADE S43°E 71.41.
- SET 5/8" REBAR & CAP CK3 LLC AT GRADE S23°W 81.36.

Sketch of Monument, Accessories and General Area

Surveyor's Seal

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Lance King

**OREGON
MAY 10, 2011
LANCE CLARK KING
61420**

RENEWS: 6/30/2015

Agency:
CK3, LLC
945 W. ORCHARD
HERMISTON OREGON 97838
OFFICE: 541-567-2345
FAX: 541-567-2305
WEB: CK3LLC.NET
Field Book # 0-289

**COUNTY SURVEYOR
RECORDING INFO**

Received 3-16-2015

Filed 3-16-2015

Survey No. 2015-1727C

Drawing No. 1727

Index No. R-13