

OREGON CORNER RESTORATION FORM

SECTION: 2 TOWNSHIP: 4N RANGE: 26E A-21

COUNTY: MORROW DATE: 11/08

CORNER DESIGNATION

NE SEC. 2

CONDITION REPORT ONLY

- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Thompson under Contract #131 in 1869. Gould did a dependent resurvey in 1939. He set Brass Caps at all G.L.O. corners.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found badly bent Iron Pipe W.C. S 6° E 20' from corner (South 16.5') Record. Did Not Use.

MONUMENT DETAIL

- T5N R26E
- S35
- S2 | S1
- T4N R26E
- CC
- 2008
- LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By retracing Gould's 1939 Survey (See My Partition Plat 2008-11) I set a 5/8" x 30" Iron Rebar with a 2" Alum. Cap stamped as above at the surface of a paved road.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 42° 17' 40" W 26.83'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 38° 07' 29" E 25.67'
- A 5/8" x 30" Iron Rebar with plastic cap # 951 bears S 6° 33' 20" E 18.04'
- A 2 3/8" Brass Cap which I set over a 1915 G.L.O. 3" Brass Cap at the SE corner of Sec. 35 T5N, R26E, bears N 89° 38' 36" E 965.79'


LOCATION AND COMMENTS

From intersection of 8TH Road West with Depot Lane go East on Depot Lane 0.8 Mile to corner..


SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: G. DENNIS EDWARDS



G. Dennis Edwards



RECEIVED BY

#Morrow County Surveyor
 Date MAY 4 2009
 Rec'd By SKB
 No. A-21