


CERTIFIED RECORD OF LAND CORNER MONUMENTATION / RESTORATION

T.4N., R.27E., INDEX N-13

History of original corner establishment:

This corner was originally established by Nicholas Walden under G.L.O. contract No. 209, dated July 6, 1874. Survey General notes state:

Drove charred stake and raised mound of earth with pits as Per instructions for Cor to Secs 15, 16, 21 & 22. Drove Willow stake 2 ft long 2 in square in SE pit.



Description of corner evidence found:

No evidence of this corner is found. Set monument at double proportionate measure.

Description of monument and accessories I establish to perpetuate the original location of this corner:

At proportionate position determined by survey, Set a 2-1/2" x 30" aluminum pipe monument with 3" dia. cap stamped as shown in the DIAGRAM, 28" in the ground, from which:

- A 5/8" rebar pin bears N57°48'08"W, 18.74 ft.
- A 5/8" rebar pin with 1 groove filed on the top, bears N68°59'23"E, 14.08 ft.
- A 5/8" rebar pin with 2 grooves filed on the top, bears S43°50'32"E, 14.76 ft.
- A 5/8" rebar pin with 3 grooves filed on the top, bears S65°08'36"W, 14.95 ft.

Place an orange plastic cap marked "FS&E Survey Marker" on all rebar pins. Set a green steel "T" post with white top 1 ft. north of monument.

Measurements to accessories taken with: Topcon Hyper II GPS (RTK)

I hereby certify that the above corner point was perpetuated as shown hereon on July 28, 2015

Witness: D. Mitchell Ferguson, LSIT
David Herburger

Office of County Surveyor County of Morrow
State of Oregon. I hereby certify that the within instrument was filed in this office
for record on the 13th day of January, 2016

Stephen K. Hallock by _____
County Surveyor Deputy

Refer to Map of Survey # 2016-1752D

DIAGRAM

T4N R27E
S16 | S15

S21 | S22
2015
PLS 49865

