

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION 33   34 4   3	TOWNSHIP T 3 S T 4 S	RANGE R 24 E, OF THE WILLAMETTE MERIDIAN	30 APRIL 06
MORROW COUNTY, OREGON			
CORNER DESIGNATION: 33   34 T 3 S 4   3 T 4 S R 24 E, OF THE WILLAMETTE MERIDIAN			
Previous Renewals / Surveys, etc.  POST SET BY THOMPSON, CONTRACT 122, 13 JUNE 1867.			
Monument(s) & Accessories Found: (Condition & Source) OREGON STATE HIGHWAY 206 EAST-WEST CENTERLINE AND A NORTH-SOUTH FENCE EXTENDED SOUTH, TO ITS INTERSECTION WITH THE HIGHWAY CENTERLINE ACCEPTED AS THE BEST REMAINING EVIDENCE OF THE ORIGINAL CORNER LOCATION.			
Monument Detail: 		Sketch: 	
Monument Set (Procedures and Description): SET PK NAIL AT INTERSECTION OF FENCE LINE EXTENDED SOUTH WITH THE CENTERLINE OF OREGON STATE HIGHWAY # 206.			
New Accessories: CORNER POSTER ON RR TIE FENCE POST S 17° W 30.25'. CORNER POSTER ON RR TIE FENCE POST N 02° W 25.06'. CORNER POSTER ON RR TIE FENCE POST S 56° E 70.41'. USGS BM "3" BRASS CAP SET IN CONC." N 10° E 25.34'.			
Location & Comments: EASY ACCESS		Compass Declination: NOT DETERMINED	
Firm / Agency COPPOCK SURVEYING PO Box 495 HEPNER, OR 97836			
Party Chief JUDSON L. COPPOCK LS 2850			
Notes SHANNON BENEFIT			
Witness			
SURVEYOR'S SEAL REGISTERED PROFESSIONAL LAND SURVEYOR		 OREGON JANUARY 20 1998 JUDSON L. COPPOCK 2850	
RENEWAL DATE: DEC. 31, 2007			