

R-15

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION 27	TOWNSHIP 4 S.	RANGE 25 E.	
MORROW COUNTY		DATE June, 2012	
CORNER DESIGNATION:			
(Please check one)			
<input type="checkbox"/> Condition Report Only			
<input checked="" type="checkbox"/> Not Found			
<input type="checkbox"/> Renewed			
<input type="checkbox"/> Unrecorded			
<input type="checkbox"/> Surveyed In			
<input type="checkbox"/> Referenced Out			
4S25R15			
<i>Previous Renewals / Surveys. etc.</i>			
Originally set by Zenas F Moody under contract No. 184, dated March 29, 1873. He set a stone 12x11x6 for the North 1/4 corner to Section 27.			
<i>Monument(s) & Accessories Found: (Condition & Source)</i>			
No evidence of the original corner found.			
<i>Monument Detail:</i>	<i>Sketch:</i>		
<i>Monument Set (Procedures and Description):</i>			
Set 1"x36" galvanized iron pipe with a 2-1/2" Brass Cap stamped as shown above, 18" in the ground and raised a mound of stone around it. Corner was set at single proportionate measure.			
<i>New Accessories:</i>			
Set four 5/8"x20" iron rods with 2" Aluminum Caps stamped Oregon Dept. of Transportation. The monument and references were ties using Leica System 1200 RTK GPS. Bearings and distances to corner as follows: RP1 - N30-47°E, 9.91 Feet, RP2 - S47-34°E, 10.27 Feet, RP3 - S36-38°W, 6.86 Feet, RP4 - N50-37°W, 10.10 Feet			
<i>Location & Comments:</i>		<i>Compass Declination:</i>	
<i>Firm / Agency</i>		SURVEYOR'S SEAL	
Oregon Department of Transportation, Geometrics Unit <input checked="" type="checkbox"/>		REGISTERED PROFESSIONAL LAND SURVEYOR	
<i>Party Chief</i>			
J. David Brinton, PLS		OREGON December 2, 1983 J. David Brinton 2065	
<i>Notes</i>		RENEWAL DATE: 12/31/13	
<i>Witness</i> Bill Dye, PLS			