

V-15

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION 27	TOWNSHIP 4 S.	RANGE 25 E.	
MORROW COUNTY		DATE June, 2012	
CORNER DESIGNATION:			
(Please check one)			
<input type="checkbox"/> Condition Report Only			
<input checked="" type="checkbox"/> Not Found			
<input type="checkbox"/> Renewed			
<input type="checkbox"/> Unrecorded			
<input type="checkbox"/> Surveyed In			
<input type="checkbox"/> Referenced Out			
4S25V15			
<i>Previous Renewals / Surveys. etc.</i>			
Originally set by Zenas F Moody under contract No. 184, dated March 29, 1873. He set a stone 14x12x8 for the South 1/4 corner to Section 27.			
Monument(s) & Accessories Found: (Condition & Source)			
No evidence of the record corner found. This corner falls in the rock fill slope of the highway. A reference monument was set 35.00 feet West of the corner position.			
Monument Detail:		Sketch:	
Monument Set (Procedures and Description):			
Set 1"x36" galvanized iron pipe with a 2-1/2" Brass Cap stamped as shown above, 30" in the ground and raised a mound of stone around it. Corner was set at single proportionate measure.			
New Accessories:			
Set four 5/8"x20" iron rods with 2" Aluminum Caps stamped Oregon Dept. of Transportation. The monument and references were ties using Leica System 1200 RTK GPS. Bearings and distances to reference monument as follows: RP1 - N39-58'E, 7.33 Feet, RP2 - S40-04'E, 10.21 Feet, RP3 - S49-25'W, 12.81 Feet, RP4 - N42-30'W, 11.26 Feet			
Location & Comments:		Compass Declination:	
Firm / Agency		SURVEYOR'S SEAL	
Oregon Department of Transportation, Geometrics Unit		REGISTERED PROFESSIONAL LAND SURVEYOR	
Party Chief		<i>J. David Brinton</i>	
J. David Brinton, PLS		OREGON December 2, 1983 J. David Brinton 2065	
Notes		RENEWAL DATE: 12/31/13	
Bill Dye, PLS			