

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 09/19/16

CORNER DESIGNATION: T4S., R26E., W.M., J-15. The North one-quarter corner of Section 15.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Deputy Surveyor Z. F. Moody under Contract No. 184, dated March 29, 1873. Notes state: Set stone 12 x 10 x 7 for 1/4 S Cor. No record of subsequent remonumentation was found in County Survey Records.

MONUMENT AND ACCESSORIES FOUND:

At a fence jack corner with fences extending West and North, found a basalt stone of record size, loose in the fence jack, found dim chisel marks depicting the corner of a small open "4". Could not make out the remainder of the markings. The fences and fence jack have been rebuilt in the recent past. Northwest of the fence jack is an old rock crib with the stones remaining but the wood rotted away. I held the Southeast corner of the old rock crib as best remaining evidence of the original corner location.

MONUMENT MARKING DETAIL:

T4S R26E
S10
1/4 -----
S15
2016
PLS 1106

RECEIVED BY
Morrow County Surveyor
Date: 10-11-2016
Rec'd By: S.K.H.
No.: 4S26J15
Folder No.: _____

MONUMENT SET:

At the Southeast corner of the old rock crib, I drove a 5/8" by 24" rebar 20" in the ground to refusal and capped with a plastic sleeved 2" aluminum cap and surrounded with a mound of stone 2 1/2 feet in diameter. The monument cap is stamped as shown in Monument Marking Detail. Placed the corner stone in the stone mound Northeast of the corner monument.

New Accessories:

- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 08° East a distance of 23.1 feet, in a fence line extending North.
- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 83° East, 27.6 feet..
- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 21° West, 32.4 feet.
- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 79° West, 34.3 feet, in a fence line extending West.

Wired Bearing Object signs to all rebar accessories. Nailed Witness sign to the fence jack corner post Southeast of corner monument.

LOCATION AND COMMENTS: Corner is located on a West facing hillside at the Southeast corner of an old rock crib just Northwest of the fence jack with fences extending North and West. Monument is 4 feet North of the fence extending West and 3 feet West of the fence extending North.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Dean Roy

4S26J-15

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-18