

R-19

### OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 03/06/07

CORNER DESIGNATION: T4S R26E., W.M., R-19. The North One-Quarter Corner of Section 26.

#### PREVIOUS RENEWALS/SURVEYS ETC.:

Original notes by Deputy Surveyor Z. F. Moody under Contract No. 184, dated March 29, 1873, state: Set stone 11 x 10 x 6 for 1/4 Sec. Cor.. No record of subsequent remonumentation was found in County Survey Records.

#### MONUMENT AND ACCESSORIES FOUND:

Fence intersection with fences East-West and North.

#### MONUMENT MARKING DETAIL:

T4S R26E

S23

1/4-----

S26

2007

PLS 1106

#### MONUMENT SET:

I accepted this fence intersection as best remaining evidence of the original corner location. Although the current fence has been rebuilt, there is evidence of older fence, (old wire and wood). The field NW of the fence corner has been farmed, but is now in CRP. I removed and inspected rocks making up the "rock jack" at this fence corner and found a couple of stones of approximate record size but could discern no chisel marks. At a point just South of the fence corner, set a 2 3/8" brass cap on 1 1/4 x 30" galvanized iron pipe 24" in the ground, marked as shown in Monument Marking Detail

#### New Accessories:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372", in a East-West fence bears North 90° West, 44.2 feet.  
A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" in a East-West fence bears North 90° West, 18.0 feet.  
A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372", in a East-West fence bears North 90° East, 12.8 feet.  
A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372", in a North-South fence bears North 00° East, 17.1 feet.  
Attached USFS "bearing tree" signs to all rebar accessories. Nailed witness sign to railroad tie post North of corner monument.

LOCATION AND COMMENTS: Corner is at a fence corner with fences East-West and North. The area surrounding the corner, except for the NE quadrant, has been farmed in the past. The corner point is on a North slope.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Micah Engum

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*

RECEIVED BY

Morrow County Surveyor  
Date APRIL 17, 2007  
Filed By SKP  
R-19

/4S26R19