

X-17

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 03/06/07

CORNER DESIGNATION: T4S., R26E., W.M., X-17. The West One-Quarter Corner of Section 35.

PREVIOUS RENEWALS/SURVEYS ETC.:

Original notes by Deputy Surveyor Z. F. Moody under Contract No. 184, dated March 29, 1873, state: Set stone 14 x 10 x 3 for 1/4 Sec. Cor.. No record of subsequent remonumentation was found in County Survey Records.

MONUMENT AND ACCESSORIES FOUND:

Found a 15" x 9" x 4" basalt stone with visible 1 and 4 lying flat in a 3' dia. mound of stone with old wood fence post fence remains running South and East. The marks on the stone are legible, but the chisel marks are very light, only about 1/32nd of an inch deep.

MONUMENT MARKING DETAIL:

T4S R26E
1/4
S34 | S35
2007
PLS 1106

MONUMENT SET:

At the position of the found stone, set a 2 inch diameter Bernsten plastic sleeved aluminum cap atop a 5/8" x 24" iron rebar driven 15" in the ground to solid bedrock. Surrounded new monument with stone and earth mound. Buried original stone on East side of new mound. Cap stamped as shown in Monument Marking Detail.

New Accessories:

- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 34° East, 24.4 feet.
- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 42° East, 29.5 feet.
- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 21 1/2° West, 27.5 feet.
- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 44 1/2° West, 22.1 feet.

Attached USFS "bearing tree" signs to all rebar accessories. Set steel fence post with witness sign attached 20 feet West of monument.

LOCATION AND COMMENTS: Corner is located approximately 150 feet West of the bottom of a draw and 30 feet East of the edge of a CRP field on a rocky East sloping hillside.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/4S26X17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

RECEIVED BY

Morrow County Surveyor

Date APRIL 17 2007

Rec'd By SKB

No. X-17