

OREGON CORNER RESTORATION FORM

COUNTY: Morrow. DATE: 03/06/07

CORNER DESIGNATION: T4S., R26E., W.M., X-21. The East One-Quarter Corner of Section 35.

PREVIOUS RENEWALS/SURVEYS ETC.:

Original notes by Deputy Surveyor Z. F. Moody under Contract No. 184, dated March 29, 1873, state: Set stone 10 x 10 x 6 for 1/4 section corner. No record of subsequent monumentation was found in County Survey Records.

MONUMENT AND ACCESSORIES FOUND:

Found a 3 foot diameter mound of stone at the at record distances South of the original calls to "road". Indications of the old road and/or the existing road, still are evident, 0.5 chains and 10.4 chains North of corner mound.

MONUMENT MARKING DETAIL:

- T4S R26E
- 1/4
- S35|S36
- 2007
- PLS 1106

MONUMENT SET:

At the position of the stone mound, I set a 2 inch diameter Bernsten plastic sleeved aluminum cap, on 5/8" by 24" iron rebar, 22" in the ground to bedrock, and surrounded with mound of earth and stone. Cap is marked as shown in Monument Marking Detail. There are old rock mound and wood pieces from a old fence, extending East, several hundred feet. There is a newer East-West fence and old, but rebuilt fence, extending South, 50 feet South of the corner point. There is a old fence extending East from Road Canyon Road, 2652 feet South of the corner point. I searched all stones in the vicinity of the corner point. Found one stone of record size in the accepted mound, but could not discern chisel marks.

New Accessories:

- A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 67 1/2° East, 67.5 feet.
 - A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 47° East, 84.1 feet.
 - A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 04° West, 51.5 feet.
 - A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 41° West, 51.3 feet.
- Attached USFS "bearing tree" signs to all rebar accessories. Set steel fence post 2 feet North of corner with witness sign attached.

LOCATION AND COMMENTS: Corner is located approximately 50 feet North of a East-West fence and 33 feet South of a old road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSJT
Micah Engum

/4S26X21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

RECEIVED BY
Morrow County Surveyor
Date April 17 2007
Rec'd By SKB
No. X-21

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08