

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 13
DIAGRAM

T4S R28E
<u>S4/S3</u>
S9/S10
PLS 1636
2002

History of original corner establishment:

The original corner was established by Zenas F. Moody in May, 1873 under GLO contract No. 184, as follows:

Set a stone, 36" x 14" x 10", for corner to sections 9, 10, 3 and 4.

Original corner evidence recovered:

Found the original corner stone loosely set. The corner stone is 30" x 17" x 7" and is plainly marked with five grooves on one (south) edge and three grooves on another (east) edge. I visited this corner in August, 1982, and found this stone set solidly in the ground at that time.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone, which broke into two pieces when I moved it, along the south side of the pipe, from which:

A 14" Ponderosa Pine, scribed "T4S R28E S3 BT" on double blazes, with a 3/4" brass washer, marked "PLS 1636", nailed flush to the base of the lower blaze, bears N28° 30' E, 95.1 feet.
A 15" Ponderosa Pine, scribed "T4S R28E S10 BT" on double blazes, with a 3/4" brass washer, marked "PLS 1636", nailed flush to the base of the lower blaze, bears S34° E, 51.9 feet.
A 9" Ponderosa Pine, scribed "T4S R28E S9 BT" on double blazes, with a 3/4" brass washer, marked "PLS 1636", nailed flush to the base of the lower blaze, bears S79° W, 22.0 feet.
A 15" Douglas-fir, scribed "T4S R28E S4 BT" on double blazes, with a 3/4" brass washer, marked "PLS 1636", nailed flush to the base of the lower blaze, bears N84° 30' W, 149.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 1, 2002. Magnetic declination set in compass: 18° E.


Dennis L. Gaylond

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Morrow County Surveyor

Date: 1-4-14
Rec'd By: S.K.H.
No.: 45 28 E 13
Folder No.: _____