

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. N-15

This original paper plat is finished in 1884, by Frank W. Campbell, under General Land Office contract No. 507. Surveyor General's Notes State: Set a post 3-1/2 ft. long, 3 ins. square, 24 ins in the ground, for 1/4 sec. cor, marked, 1/4 S on N face, from which A tamarack 24 ins. in diam bears N50°E., 5 lks dist. A fir 8 ins. in diam bears S40°E., 16 lks. dist. marked 1/4 S BT. In 1982 the Bureau of Land Management, re-monumented the corner from existing original evidence.

DIAGRAM
R28E
S15
1/4-----
S22
1982
BLM


Description of corner evidence found:
Found a 3-1/2" aluminum cap monument, stamped as shown on the **DIAGRAM**

Found original bearing tree, a Fir, live in good condition, Bears, S40E., 10.2 ft.,
Found bearing tree taken by the BLM in 1982, live in good condition.

Description of monument and accessories established to perpetuate the

original location of this corner:
Maintained Corner by setting a steel post with warning sign East 1.5 ft. from the corner.

Maintained Accessories as follows:
Nailed Bearing tree sign above blaze, and warning sign on back of the original Bearing Tree.
Nailed a Warning sign on Bk. of tree taken in 1982.
Painted a 6" red band at breast ht. around both trees.



Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.
On July 25, 1984
Witnessed by J. David Brinton, PLS 2065

Office of Suresya County of Morris
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 19th day of September, 1988
by David H. Kumbeln (COUNTY OFFICIAL) David Reynolds (DEPUTY)

RECEIVED BY
Morrow County Surveyor
Date 1-10-86
Rec'd by MLD
No. 281-R