


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. N-5

History of original corner establishment:

Corner originally established in 1873, by Zenas F. Moody, under General Land Office Contract No. 184. Surveyor Generals Notes State: Set post in Stone mound for cor. to Secs. 19-20-17-18, from which:
A Pine 10 in dia. bears, S 5⁰E., 7 lks.
A Pine 20 in dia. bears, N50⁰E., 30 lks.



Description of corner evidence found:

Corner is on a steep south slope, all evidence of the post and stone mound have eroded and slid downhill.

Found a Pine, 16" dia., live in good condition with blaze open and scribing visible, but not legible.


Set corner position at Record N 5W., 4.6 ft. from blaze face of above found tree.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 24" in the ground, and raised a mound of stone & earth around the pipe.

From which:

- A Pine 14" dia. Bears, N40⁰W., 82.6 ft., scribed: T4S R28E S18 BT
 - A Pine 16" dia. Bears, N80⁰E., 42.4 ft., scribed: T4S R28E S17 BT
 - A Pine 12" dia. Bears, S34⁰E., 39.2 ft., scribed: T4S R28E S20 BT
 - A Pine 12" dia. Bears, S 8⁰W., 42.2 ft., scribed: T4S R28E S19 BT
- Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.
Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning sign, North 1 ft. from the corner.



Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.
On Aug. 15, 1984
Witnessed by J. David Brinton, PLS 2065

Office of..... Surveyor..... County of MORRIS.....
State of Oregon..... I hereby certify that the within instrument was filed in this office
for record on the 10th day of September, 1985
by David H. Keumbein..... David H. Keumbein
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Morrow County Surveyor

★ OPO-798-276

Date 1-10-86
Rec'd By MLD
No. 768-K