

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-5

History of original corner establishment:

Corner originally established in 1875, by Zenas F. Moody, under General Land Office Contract No. 194. Surveyor General's Notes State: Set a stone 24x20x12 for cor. to Secs. 29-30-19-20.

DIAGRAM	
T4S R28E	
S191S20	

S301S29	
1984	
PLS 848	

Description of corner evidence found:

Found a 22"x20"x12" granite stone, with 5 grooves on the East face & 2 grooves on the South face, when stone is set upright. Set in a N&E fence corner.

No accessories originally established. Even though the stone is not set, it is accepted as the Section Corner position, as it is so large that it could not have been moved far. It also looks like the fence constructed through the corner.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 12" in the ground, set original stone east, alongside pipe and raised a mound of stone and earth around the pipe.

From Which:

A Pine 12" dia. Bears, N55°W., 32.6 ft., scribed: T4S R28E S19 BT

A Pine 10" dia. Bears, N63°E., 29.6 ft., scribed: T4S R28E S20 BT

A Pine 10" dia. Bears, S11°E., 32.6 ft., scribed: T4S R28E S29 BT

A Fir 14" dia. Bears, S36°W., 25.5 ft., scribed: T4S R28E S30 BT

Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.

Nailed a brass washer stamped PLS 848 on blaze above RT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning sign, North 5 ft. from the corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
O'REGON
JULY 12, 1966
DOUGLAS M. FERGUSON
848

Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore
On Aug. 15, 1984
Witnessed by J. David Brinton, PLS 2065

Office of Sullivan County of McClain

State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 10th day of September, 1985
David H. Krumbein by B. Brinton Deputy
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Monroe County Surveyor

Date 1-10-86

Rec'd by M.L.D.

No. 777-E