

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. R-9

History of original corner establishment:

Corner originally established in 1873, by Zenas F. Moody, under General Land Office Contract No. 184. Surveyor General's Notes State: Set post in Earth mound for cor. to Secs. 28-29-20-21

<b>DIAGRAM</b>	
T4S R28E	
S201S21	
---	
S291S28	
1984	
PLS 848	


Description of corner evidence found:

No evidence is found, corner has been lost to old logging activity.

No accessories originally established. Established the corner position at proportionate measure from corner found 1 mi. North, East & West and 1/2 mi. South.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 24" in the ground.  
From which,  
A Pine 10" dia. Bears, N70W., 56.0 ft., scribed: T4S R28E S20 BT  
A Pine 10" dia. Bears, N71E., 75.6 ft., scribed: T4S R28E S21 BT  
A Pine 12" dia. Bears, S24E., 55.0 ft., scribed: T4S R28E S28 BT  
A Pine 8" dia. Bears, S13-1/2W., 34.1 ft., scribed: T4S R28E S29 BT  
Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.  
Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning sign, North 2 ft. from the corner.



Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.  
On Aug. 2, 1984  
Witnessed by J. David Brinton, PLS 2065

Office of..... *Silverfork*..... County of..... *Morrow*.....  
State of *Oregon*..... I hereby certify that the within instrument was filed in this office  
for record on the *10th* day of..... *September*....., 19*85*  
..... *David H. Kumbrein*..... by..... *David*..... *Reynolds*.....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Morrow County Surveyor

*1-10-86*

*1087MID*

*263-K*