

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-15

History of original corner establishment:

Corner was established in 1968, by Donald L. Staebler, as shown in the Morrow County Surveyors Records, as Survey No. 204-K. That map of survey States: Set 2" Iron pipe.

DIAGRAM  
145 R28E  
C1/4  
S27  
1984  
PLS 848

Description of corner evidence found:

Found a 2" iron pipe projecting above the ground 4"

No accessories established by Staebler in 1968.

Found the pipe, N 30° 36' E., 12.9 ft. from the intersection of the four 1/4 corners of sec. 27, therefore did not accept the said pipe as the C-1/4 Corner position.


Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 18" in the ground, and raised a mound of stone and earth around the pipe.

From Which:

A Lodgepole Pine 12" dia. Bears, N170°E 11.1 ft., scribed: C1/4 S27 BT  
A Lodgepole Pine 12" dia. Bears, S120°E 22.2 ft., scribed: C1/4 S27 BT  
Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.

Nailed a brass washer stamped PLS 848 on blaze above RT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning sign, North 2 ft. from the corner.



Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.  
On Aug. 1, 1984  
Witnessed by J. David Brinton, PLS 2065

Office of..... *Surrogate* ..... County of *Morrow* .....  
State of *Oregon* ..... I hereby certify that the within instrument was filed in this office  
for record on the *12th* day of *September*, 1985  
*David H. Krueber* ..... by *Brent Reynolds*  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Morrow County Surveyor  
Date *1-10-86*  
Rec'd By *MLD*  
No. *778-K*