


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. T-16
History of original corner establishment:

Corner not previously established.




Description of corner evidence found:

Corner not previously established.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 24" in the ground.
From which.
A Fir 20" dia. Bears, N73W., 38.1 ft., scribed: C-E 1/16 S27 BT
A Pine 12" dia. Bears, S69E., 49.3 ft., scribed: C-E 1/16 S27 BT
Measurements to trees taken with a metal tape and magnetic compass, with Declination set of 20 deg. East.
Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North & South 5 ft. from the corner.



Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.
On July 31, 1984
Witnessed by J. David Brinton, PLS 2065

Office of SURVEYOR..... County of MORROW.....
State of OREGON....., I hereby certify that the within instrument was filed in this office
for record on the 30th day of September, 1984
David H. Krumbein..... by Brinton Raymond
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECORDED BY
MORROW COUNTY SURVEYOR
Date 1-10-86
Rec'd by MLD
No. 998-R