

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. V-11

History of original corner establishment:

Corner originally established in 1873, by Zenas F. Moody, under General Land Office Contract No. 184, Surveyor General's Notes State; Set a post in a stone mound for 1/4 S Cor.

| DIAGRAM  |  |
|----------|--|
| T4S R28E |  |
| S28      |  |
| 1/4-.-   |  |
| S33      |  |
| 1984     |  |
| PLS 848  |  |

Description of corner evidence found:

No evidence is found there are no stones in the area it is possible that this corner was never set.

No Accessories originally established. Corner is established by single proportionate measure, from proportioned section corner 1/2 mi. west & section corner as found 1/2 mi. east from this position.


Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 28" in the ground.

From which.

A Fir 9" dia. Bears, N60°E., 10.7 ft., scribed: 1/4 S28 BT  
 A Fir 14" dia. Bears, S 8°W., 9.6 ft., scribed: 1/4 S33 BT  
 Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East;

Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning sign, North 1.5 ft. from the corner.



Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.  
 On Aug. 7, 1984  
 Witnessed by J. David Brinton, PLS 2065

Office of..... Sullivan ..... County of Madras .....  
 State of Oregon ..... I hereby certify that the within instrument was filed in this office  
 for record on the 12th day of September ..... 1985  
David H. Krumboltz by Raymond L. ...  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
 Morrow County Surveyor  
 Date 1-18-86  
 Rec'd BY M.L.D.  
 No. 779-K

Form R6-7100-57 (9/71)