

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. V-13

**History of original corner establishment:**

Corner originally established in 1873, by Zenas F. Moody, under General Land Office Contract No. 184. Surveyor Generals Notes State: Set a post in stone mound for cor. to Secs. 33-34-27-28.

<b>DIAGRAM</b>
T4S R28E
S281927
---
S331934
1984
PLS 848

**Description of corner evidence found:**

Found an old mound of stone with soft, discolored earth in the center where the post stood.

No accessories originally established. This is the same mound of stone as called for by Donald L. Staebler, in his survey of 1968 (see Morrow County Survey Records, Survey No. 204-K) Accepted the Center of the mound as the Section. Corner position.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 26" in the ground and placed a ring of stone and earth around the pipe.

From which:  
A Fir 12" dia. Bears, N56°W., 29.3 ft., scribed: T4S R28E S28 BT  
A Tamarack 14" dia. Bears, N51°E., 41.9 ft., scribed: T4S R28E S27 BT  
A Tamarack 14" dia. Bears, S53°E., 20.4 ft., scribed: T4S R28E S34 BT  
A Fir 10" dia. Bears, S26°W., 35.0 ft., scribed: T4S R28E S33 BT  
Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.  
Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, North 5 ft. & West approx. 50 ft. from the corner.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
JULY 12, 1988  
DOUGLAS M. FERGUSON  
848

Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.  
On Aug. 1, 1984  
Witnessed by J. David Brinton, PLS 2065

Office of..... *[Signature]* Surveyor..... County of..... *[Signature]*  
State of Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the 10th day of..... *[Signature]*..... 1985  
..... *[Signature]* by..... *[Signature]* Deputy  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Morrow County Surveyor  
Date 1-15-86  
No. 762-K