

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Fenland 1988 Cadastral Survey
Section 33, T.4S., R.28E., W.M.

W-10

History of original corner establishment:

No record of previous monumentation.

DIAGRAM
T4S R28E
NW1/16 S33

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the

original location of this corner:

At the corner point I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap

NW1/16 S33
PLS 1832
1988

Monument is 24" in the ground.

From the corner:

A Lodgepole Pine, 9" dia., S39°W, 28.8 ft.; marked: NW1/16 S33 BT

A Lodgepole Pine, 9" dia., N66 1/2°W, 80.8 ft.; marked: NW1/16 S33 BT

BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass, Magnetic declination set at 18°E.

June 22, 1988

RECEIVED BY

Morrow County Surveyor

Date 11/1/88

Rec'd By LORIK

No. C 873K

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

