

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Plat of Penland 1988 Cadastral Survey
Section 33, T.45., R.28E., W.M.

W-12

History of original corner establishment:
No record of previous monumentation.

DIAGRAM
T4S R28E
NE1/16 S33

Description of corner evidence found:
None.

Description of monument and accessories | established to perpetuate the
original location of this corner:
At the corner point I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap
containing a magnet and marked:
NE1/16 S33
PLS 1832
1988
Monument is 22" in the ground and surrounded
by a mound of stone.

From the corner:
A Douglas Fir, 10" dia., S30 1/4° W, 12.8 ft.; marked: NE1/16 S33 BT
A White Fir, 17" dia., S46 1/4° E, 46.8 ft.; marked NE1/16 S33 BT
BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument"
signs and alum. "PLS 1832" washers nailed to the bottom of the blaze.
There is a 6' steel fence post with a "Land Survey Monument" sign within
5' of the corner.
Measured to center of BTs using steel tape and staff compass. Magnetic
declination set at 180E.
June 30, 1988

RECEIVED BY
Morrow County Surveyor

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Date 11/6/88
Rec'd By LODK
No. 273K
Fayette S. Munro
REGISTERED
PROFESSIONAL
LAND SURVEYOR
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)