

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Refer to: Penland 1988 Cadastral Survey
Section 33, T.49 S.; R.28E.; W.M.

X-10

History of original corner establishment:
No record of previous monumentation.

DIAGRAM
T49 R28E
W1/16
C-----C
S33

Description of corner evidence found:
None.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap containing a magnet and marked:

Monument is 25" in the ground. W1/16
C-----C

From the corner: S33
PLS 1832
1988

A White Fir, 25" dia., 35 1/2' W.; 71.8 ft.; marked: CW1/16 S33 BT
A White Fir, 19" dia., 378 1/2' E., 37.3 ft.; marked: CW1/16 S33 BT

BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 17°E.

June 22, 1988

RECEIVED BY

Morrow County Surveyor

Date 11/188

Rec'd By OHK

No. C873K

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro
OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by (DEPUTY)
(COUNTY OFFICIAL)