

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. X-23

History of original corner establishment:

Corner not previously established.

X-23

| | |
|----------------|--|
| DIAGRAM | |
| T4S R28E | |
| C1/4 | |
| 536 | |
| 1984 | |
| PLS 848 | |

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 24" in the ground.
 From which,
 A Tamarack 8" dia. Bears N78⁰⁰E., 6.0 ft., scribed: C1/4 S36 BT
 A Spruce 14" dia. Bears S13⁰⁰W., 6.9 ft., scribed: C1/4 S36 BT
 Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.
 Nailed a brass washer stamped PLS 848 on blaze above BT scribe; Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning % Boundary Signs, South & East 5 ft. from the corner.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

[Signature]

OREGON
 JULY 12, 1968
 DOUGLAS M. FERGUSON
 848

Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.
 On July 25, 1984
 Witnessed by J. David Brinton, PLS 2065

Office of... *Susweyer*^{1/4} County of... **MARION**

State of... **Oregon** ... I hereby certify that the within instrument was filed in this office
 for record on the... 10th day of... **September**... **1985**

... **David H. Krumbein** by... **Brent Reynolds**
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Marion County Surveyor

Date 1-10-86

Recd by **M.L.D.**

No. 754-K

Form R6-7100-57 (9/71)