

INDEX No. Z-23

**DIAGRAM** on cap)

(T4S R28E)

1/4 S36

1938  
GLD

**History of original corner establishment:**

Corner originally established in 1881, by Edward W. Sanderson, under General Land Office Contract No. 417. Surveyor Generals Notes State: Set a sandstone 18x8x7 ins. 12 ins. in ground for 1/4 Sec. Cor. marked 1/4 on N face. A Black pine 12 in. dia. bears North 10 lks. dist. marked 1/4 S BT

A fir 4 in. dia. bears S10°W. 5 lks. dist. marked 1/4 S BT

In 1938 Leonard Carter, Cadastral Engineer for the "General Land Office" performed a Dependent Resurvey. Those Notes State: The 1/4 sec. cor. of sec. 36 only, which is a basalt stone, 14x8x6 ins., firmly set, mkd. 1/4 on N. face; nor accessories. (found) At point for corner, Set an iron post 3 ft. long, 1 in. dia., 28 ins. in the ground, with the original stone deposited at the base, for 1/4 sec. cor. of sec. 36 only, with brass cap mkd. (see **DIAGRAM**) from which A fir 8" bears N39°E, 50 lks. mkd. 1/4 S36 BT

A Spruce 20" bears N55°W., 125 lks. mkd. 1/4 S36 BT.

**Description of corner evidence found:**

Found a 1" iron pipe with 2-1/2" brass cap, stamped as shown on the **DIAGRAM**, set 6" above the ground.

Found the Bearing trees as taken by Carter in 1938, dead, new accessories are needed.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Maintained corner by setting a steel post with warning sign, North 1.5 ft. from the corner.

Maintained accessories by painting a 6" red band around existing dead trees and nailing the proper Bearing tree and warning signs to the existing trees

Scribed New Bearing Trees as follows:

A Spruce 12" dia. Bears N55°W., 6.2 ft., scribed: 1/4 S36 BT

A Spruce 12" dia. Bears N51°E., 36.7 ft., scribed: 1/4 S36 BT

Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.

Nailed a brass washer stamped PLS 848 on blaze above BT scribe; Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.  
On July 5, 1984  
Witnessed by J. David Brinton, PLS 2065

2

Office of... SURVEYOR ..... County of... WANTON .....

State of... OREGON ..... I hereby certify that the within instrument was filed in this office  
for record on the... 10... day of... September... 1985

... David H. Krumbein by... Samuel Reynolds  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

\*GPO—799-276

1-10-86  
MUD  
76D-K