

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. A-7

History of original corner establishment:

Corner not previously established.


<b>DIAGRAM</b>	
T4S R29E	---
	1/4 S5
	T5S
	1984
	PLS 848

Description of corner evidence found:

Corner not previously established.  
Corner is established at midpoint, on line between the NW & NE corners of Sec. 5.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 2-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 26" in the ground.  
From Which,  
A Fir 12" dia. Bears, S30<sup>0</sup>E., 36.4 ft., scribed: 1/4 S5 BT  
A Fir 14" dia. Bears, S10<sup>0</sup>W., 32.2 ft., scribed: 1/4 S5 BT  
Measurements to trees taken with a metal tape and magnetic compass, with Declination set off 20 deg. East.  
Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence posts with warning & Boundary Signs, East & West 5 ft. from the corner.



RECEIVED BY  
Morrow County Surveyor  
Date 1-10-86  
Book PLS MLD  
Page 739-K  
Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.  
On Aug. 8, 1984  
Witnessed by J. David Brinton, PLS 2065

Office of SURVEYOR County of MORROW  
State of Oregon I hereby certify that the within instrument was filed in this office  
for record on the 10<sup>th</sup> day of September, 1985  
by David H. Kumbel (DEPUTY)  
David H. Kumbel (COUNTY OFFICIAL)