

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. 2-9

2-9

**History of original corner establishment:**

Corner originally established in 1873, by Zenas F. Moody, under General Land Office Contract No. 184. Surveyor Generals Notes State: Set a post in Earth Mound for cor. to secs. 32-33-4-5. From which:

A Fir 12 in. diam. Bears N45°E., 15 lks.  
A Fir 8 in. diam. Bears N71°W., 20 lks.

In 1938 Leonard Carter, Cadastral Engineer for the "General Land Office" performed a Dependent Resurvey, Those Notes State: Post set for cor. and distance from the original NE Bearing tree. At the point for corner., Set an iron post, 3 ft. long, 2 ins. diam., 28 ins. in the ground for cor. of sec. 32 and 33 only, with brass cap mkd., (See DIAGRAM), from which:

A fir 15 ins. diam., bears N50°E., 17 lks. with incomplete scribe mks. (old B)  
A fir 10 ins. diam., bears N27°E., 60 lks. mkd. T4S R28E S33 BT (new BT)  
A tamarack 20 ins diam., bears N84-1/2°W., 123 lks. mkd. T4S R28E S32 BT

**Description of corner evidence found:**

Found 2" iron pipe with a 2-1/2" brass cap stamped as shown on the **DIAGRAM**, set 8" above the ground.

Found a Tamarack 24" dia., as scribed in 1938 resurvey  
11y8: in good condition with blaze healed over, Bears N28°E., 27.3 ft. (Record: Fir, N27°E., 39.6 ft.)  
Found a Fir 20" dia. as scribed in 1873, by Moody, live in good condition, with blaze healed over, Bears N50°E., 1456 ft. (Record from original survey: Fir 8" diam., N45°E., 9.9 ft.) (Record from 1938 Resurvey: Fir 15" diam., N50°E., 11.2 ft.)

**Description of monument and accessories established to perpetuate the maintained corner by setting steel posts with warning and boundary signs original location of this corner 6 ft. from the corner.**

Maintained Accessories by nailing Bearing Tree Signs above blazes and warning signs to back of above described trees and painting a 6" red band at breast h around each tree.  
Measurements to trees taken with a metal tape and magnetic compass, with Declination set of 20 deg. East.

**PREPARED BY**

Morrow County Surveyor

1-10-86

W. M. L. D.

744-K

Work by D.M. Ferguson, PLS 848, Mt. Vernon Ore.  
On Aug. 8, 1984  
Witnessed by J. David Brinton, PLS 2065

2

Office of Surveyor County of Morrow  
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 10 day of September, 1986  
by David H. Krumbein by David Reynolds  
(COUNTY OFFICIAL) (DEPUTY)