

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: A-1

Northwest closing corner of Section 6, Township 4 South, Range 29 East, W.M.
 The original township line was run in 1872 by Williams under Contract 176. The closing corner was set by Sanderson under Contract 417 in 1881.

Sanderson's record states:
 Set stone 18x12x6 with stone mound.

1	DIAGRAM	1
1	T3S R29E	1
1	S31	1
1	---	1
1	S1 S6	1
1	T4S	1
1	CC	1
1	R28E R29E	1
1	1996	1
1	PLS 852	1

Description of corner evidence found:
 Found original stone with well chiseled notches on corners in mound of stone.

Description of monument and accessories I established to perpetuate the original location of this corner:
 At the position of the record stone, I set a 30" x 1.25" GIP with a 2.25" brass cap 20" in the ground stamped as shown in the diagram above. I built a mound of stone around the monument.
 I set 5/8" x 24" pins with red plastic cap stamped ORLS 0852 and WALIS 13922 as bearing objects:
 A pin bears N0°35'E, 45.68'.
 A pin bears S89°02'E, 53.02'.
 A pin bears S0°56'W, 45.57'.
 A brass cap monumenting the position of the township corner for Ranges 28 and 29 East of Township 3 South bears S89°27'24"W, 177.59'.

This work was done October 21, 1996.

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

David L. Haddock

**OREGON
 JULY 12, 1968
 DAVID L. HADDOCK
 852**

Office of OREGON, I hereby certify that the within instrument was filed
 State of OREGON, County of MORROW
 in this office for record on the 18th day of November, 1996.
SKB by SKB
 (COUNTY OFFICIAL) (DEPUTY)