

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: A-3

North quarter corner of Section 6, T.4S., R.29E., W.M.

This corner was not previously set.

1	DIAGRAM	1
1	T3S R29E	1
1	1	1
1	- - -	1
1	4 S6	1
1	T4S R29E	1
1	1996	1
1	PLS 852	1

Description of corner evidence found:

The following original corners were found along the line between Townships 3 and 4 South; the southwest corner of Section 31, the northwest closing corner of Section 6, the south quarter corners of Sections 31 and 32, and the southeast corner of Section 32. The position for the missing corner for Sections 31 and 32 was computed proportionally on a longitudinal line between the south quarter corners of Sections 31 and 32. The positions for the northeast closing corner of Section 6 was computed at record distance from the location for the computed corner of Sections 31 and 32 because of evidence that Sanderson set the closing corners for sections to the south by only measuring east from a single section corner for Township 3 South. The quarter corner for Section 6 was set at a longitudinal position halfway between the northeast and northwest section corner positions for Section 6.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the computed position, I set a 30" x 1.25" GIP with a 2.25" brass cap 24" in the ground stamped as shown in the diagram above.

I built a mound of stone around the monument.

Marked the following witness trees:

A 10" Douglas Fir bears N22°20'E, 19.94' scribed 1/4S6BT.

A 9" Ponderosa Pine bears S3°45'E, 35.84' scribed 1/4S6BT.

A 7" Ponderosa Pine bears S46°10"W, 19.90' scribed 1/4S6BT.

The south quarter of Section 31 bears S89°47'33"W, 154.24'.

The distances and bearings are measured to the head of a nail attaching a brass washer stamped ORLS852 and WALSI3922 between the letters B and T on each tree.

This work was done October 18, 1996.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David L. Haddock

**OREGON
JULY 12, 1988
DAVID L. HADDOCK
852**

Office of _____ County of MORROW

State of OREGON, I hereby certify that the within instrument was filed in this office for record on the 18th day of NOVEMBER, 1996.

SKB (COUNTY OFFICIAL) by _____ (DEPUTY)