

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: C-1

West one quarter corner Section 6, T.4S., R.29E.,  
W.M.

This corner was set by Sanderson under contract 417  
in 1881.

His record reads:

Set a 15x9x6 stone from which:  
A 30" Fir bears S80°E, 52 lks.  
A 30" Pine bears S85°W, 52 lks.

1	DIAGRAM	1
1	T4S	1
1	1	1
1	-	1
1	R 4	R 2
1	2	2
1	8	S6 9
1	E	E
1	1996	1
1	PLS 852	1
1		1

Description of corner evidence found:

None.  
Found the original stone in a small mound of stone at the foot of a  
steel fence post with a BLM tag.  
A stump hole with rotted fir roots was found S80°E, 52 links.  
A Ponderosa Pine stump was found S85°W, 52 links with a BLM Bearing Tree  
tag. There was no visible scribing.

Description of monument and accessories I established to perpetuate the  
original location of this corner:

At the position of the record stone, I set a 30" x 1.25" GIP with a  
2.25" brass cap 28" in the ground stamped as shown in the diagram above.  
I built a mound of stone around the monument.

Marked the following witness trees:

A 7" White Fir bears N71°59'E, 33.68' scribed 1/4S6BT.  
A 12" Ponderosa Pine bears S84°10'E, 45.88' scribed 1/4S6BT.  
A 8" Western Larch bears S40°27"W, 61.14' scribed 1/4SBT.  
A 14" Douglas Fir bears N12°27'W, 23.02' scribed 1/4SBT.

The distances and bearings are measured to the head of a nail attaching  
a brass washer stamped ORLS852 and WALSI3922 between the letters B and  
T on each tree.

This work was done October 18, 1996.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*David L. Haddock*

**OREGON  
JULY 12, 1988  
DAVID L. HADDOCK  
852**

Office of \_\_\_\_\_ County of MORROW  
State of OREGON, I hereby certify that the within instrument was filed  
in this office for record on the 18<sup>th</sup> day of NOVEMBER, 1996.  
SKB by \_\_\_\_\_  
( COUNTY OFFICIAL ) ( DEPUTY )