

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: C-3

Center one quarter corner Section 6, T.4S., R.29E.,
W.M.
This corner was not previously set.

1	DIAGRAM	1
1	T4S R29E	1
1	C 1/4	1
1	1	1
1	-.-	1
1	1	1
1	S6	1
1	1	1
1	1996	1
1	PLS 852	1
1		1

Description of corner evidence found:

None.

The position of the corner set was computed as the intersection of lines between the found east and west one quarter corners of Section 6 and the found south one quarter corner of Section 6 and the computed north one quarter of Section 6.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the computed position, I set a 30" x 1.25" GIP with a 2.25" brass cap 28" in the ground stamped as shown in the diagram above.

Marked the following witness trees:

A 11" Western Larch bears N22°10'E, 102.97' scribed C1/4S6BT.

A 7" White Fir bears N49°59'E, 43.77' scribed C1/4S6BT.

A 9" White Fir bears S12°12"W, 26.01' scribed C1/4S6BT.

A 11" White Fir bears N85°43'W, 17.89' scribed C1/4S6BT.

The distances and bearings are measured to the head of a nail attaching a brass washer stamped ORLS852 and WALSI3922 between the letters B and T on each tree.

This work was done October 21, 1996.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David L. Haddock

**OREGON
JULY 12, 1968
DAVID L. HADDOCK
852**

Office of _____ County of MORROM
State of OREGON, I hereby certify that the within instrument was filed
in this office for record on the 18th day of NOVEMBER, 1996.
SKB by _____
(COUNTY OFFICIAL) (DEPUTY)