

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: C-5

Quarter corner common to Sections 5 and 6, T.4S., R.29E., W.M.
 The township was subdivided by Sanderson under contract 417 in 1881.
 His record states:
 Set stone 18x8x5 ins marked 1/4 with stone mound.

1	DIAGRAM	1
1	T4S R29E	1
1	1	1
1	-	1
1	4	1
1	S5	1
1	S6	1
1	1996	1
1	PLS 852	1
1		1

Description of corner evidence found:

Found the record stone with sharply chiseled 1/4 in a stone mound.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the original stone, I set a 30" x 1.25" GIP with a 2.25" brass cap 26" in the ground stamped as shown in the diagram above. I built a mound of stone around the monument.

Marked the following witness trees:
 A 10" Ponderosa Pine bears N17°34'E, 12.89' scribed 1/4S5BT.
 A 10" Ponderosa Pine bears S14°21'E, 42.13' scribed 1/4S5BT.
 A 9" Ponderosa Pine bears S62°09'W, 6.41' scribed 1/4S6BT.
 A 9" Ponderosa Pine bears N19°16'W, 23.40' scribed 1/4S6BT.
 The distances and bearings are measured to the head of a nail attaching a brass washer stamped ORLS852 and WALSI3922 between the letters B and T on each tree.

This work was done October 21, 1996.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

David L. Haddock

OREGON
 JULY 12, 1988
 DAVID L. HADDOCK
 852

Office of _____ County of MORRIS
 State of OREGON, I hereby certify that the within instrument was filed
 in this office for record on the 18TH day of NOVEMBER, 1996.
SKB by _____
 (COUNTY OFFICIAL) (DEPUTY)