

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 21
DIAGRAM

T4S R29E
S2S1
S11S12
PLS 1636
2000

History of original corner establishment:

The original corner was established by Edward W. Sanderson on August 18, 1882, under GLO contract No. 417, as follows:

Set a basalt stone, 18" x 12" x 6", 12" into the ground for the corner to sections 1, 2, 11 and 12, marked with 5 notches on the south and 1 notch on the east edges. Raised a mound of stones alongside.

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is a conglomerate stone, 19" x 12" x 5", and is faintly marked with 5 notches on one edge. Also found the tip of a decayed post which was driven into the ground along the east side of the corner stone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram, above. I bury the corner stone along the northeast side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S1", attached at ground level, bears N41° 30'E, 74.5 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S12", attached at ground level, bears S53°E, 128.2 feet.
- A 26" Ponderosa Pine scribed "T4S R29E S11 BT" on double blazes with a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", bears S22°W, 217.1 feet. I nail a "Bearing Tree" sign above the blazes.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears N35° 30'W, 76.5 feet.
- A fence corner, with fences projecting north, west and southeast, bears S65°W, 60.0 feet.
- A logging road, traversing east and west, bears south, 45 feet.

I hereby certify the above corner point was perpetuated as hereon described on July 28, 2000. Magnetic declination set in compass: 18°E.

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: