

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: E-3

South one quarter corner Section 6, T.4S., R.29E.,
W.M.,
Section 6 was subdivided by Sanderson under contract
417 in 1881.

1	DIAGRAM	1
1	T4S R29E	1
1		1
1	1 S6	1
1	--	1
1	4 S7	1
1		1
1		1
1	1996	1
1	PLS 852	1
1		1

His record states:
Set stone 12x12x7 with stone mound.

Description of corner evidence found:
Found original stone with well chiseled 1/4 in mound of
stone with steel fence post and attached BLM poster.

Description of monument and accessories I established to perpetuate the original location of this corner:
At the position of the record stone, I set a 30" x 1.25" GIP with a 2.25" brass cap 20" in the ground stamped as shown in the diagram above. I built a mound of stone around the monument.
I set 5/8" x 24" pins with red plastic cap stamped ORLS 0852 and WALS 13922 as bearing objects:
A pin bears S62°59'E, 44.10'.
A pin bears S24°06'W, 50.08'.
A pin bears N61°37'W, 48.86'.
An 3.5" aluminum cap, monumenting the Forest Service trinagulation point Blake, bears N21°37'00"E, 478.98'.

This work was done October 21, 1996.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David L. Haddock

OREGON
JULY 12, 1988
DAVID L. HADDOCK
852

Office of _____ County of MORROW
State of OREGON, I hereby certify that the within instrument was filed
in this office for record on the 18th day of NOVEMBER, 1996.
D.L.H. by SKB
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)