

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: E-9

Corner common to Sections 4, 5, 8 and 9, T.4S., R.29E., W.M.
 The township was subdivided by Sanderson under contract 417 in 1881.
 His record states:
 Set a sandstone 18x8x6 from which:
 A Fir 12" dia bears N60°E, 28 lks marked T4SR29ES4BT.
 A Fir 8" dia bears N20°W, 18 lks marked T4SR29ES5BT.
 A Fir 15" dia bears S15°W, 54 lks marked T4SR29ES8BT.
 A Fir 6" dia bears S84°W, 42 lks marked T4SR29ES9BT.

1	DIAGRAM	1
1		1
1	T4S R29E	1
1	S5 S4	1
1	--	1
1	S8 S9	1
1	1996	1
1	PLS 852	1
1		1

Description of corner evidence found:
 Found a fir snag scribed T4SR29ES8BT with letters BT on stump and remainder of snag, showing remainder of scribe, broke off and down hill.
 Found badly rotted stump of BT N60°E.

Description of monument and accessories I established to perpetuate the original location of this corner:
 At record distance from the two BT's, I set a 30" x 2.25" aluminum pipe with a 2.5" aluminum cap 24" in the ground stamped as shown in the diagram above. I built a mound of stone around the monument.
 Marked the following witness trees:
 A 17" Western Larch N80°00'E, 94.45' scribed T4SR29ES4BT.
 A 9" Douglas Fir bears S17°22'E, 8.27' scribed T4SR29ES9BT.
 A 7" Ponderosa Pine bears S37°36"W, 25.92' scribed T4SR29ES8BT.
 A 24" Ponderosa Pine bears N1°07'W, 33.23' scribed T4SR29ES5BT.
 The distances and bearings are measured to the head of a nail attaching a brass washer stamped ORLS852 and WALSI3922 between the letters B and T on each tree.

This work was done October 22, 1996.

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

David L. Haddock

**OREGON
 JULY 12, 1968
 DAVID L. HADDOCK
 852**

Office of OREGON, I hereby certify that the within instrument was filed in this office for record on the 18th day of NOVEMBER, 1996.
 County of MORROW
 by SKB (COUNTY OFFICIAL)
 (DEPUTY)