

G-21

History of original corner establishment:

Corner established in 1882 by Edward W. Sanderson under General Land Office Contract No. 417. Surveyor General's records state:
 A point 300 ft. below Sec. Cor.
 Set basalt stone 12x10x6 ins, 8 ins. in ground for 1/4 Sec. Cor. marked 1/4 on W face.
 From which
 A fir 3 ins. dia. bears N50°E 8 lks. dist. marked 1/4 S BT.
 A fir 6 ins. dia. bears N70°W 7 lks. dist. marked 1/4 S BT,

PLS 829E
 1/4
 1981
 5 11 15 12
 PLS 848

Description of corner evidence found:

Found 12 in. x 10 in. x 6 in. stone with 1/4 visible, sitting loose, call to cr. 1/2 chain South fits. Original bearing trees have long since rotted away (3" x 6" fir trees). Accepted center of stone as 1/4 cor. position.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 24 inches in the ground and placed original stone West alongside pipe.
 From which:
 A fir 15 in. dia. bears N28°W, 16.9 ft. scribed 1/4 S 11 BT.
 A fir 9 in. dia. bears S18°E, 14.7 ft. scribed 1/4 S 12 BT.
 Set a steel post with warning sign 5 ft. North from corner.
 Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was reestablished as herein described, on 9/3/81.

Witnesses:

MIKE WOODS BTB

JEFF SMITH

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

OREGON
 JULY 12, 1968
 DOUGLAS M. FERGUSON
 848

Office of S.D. SURVEYOR..... County of..... Yamhill
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 17th day of January, 1982
 David Kenneth Burrows (COUNTY OFFICIAL) Shasta (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

* OPO-198-276

Morrow County Surveyor

Date January 7, 1982

Rec'd By M. Hughes

No. 454-1

WWW1 NO (147-X