

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

---

History of original corner establishment:

Index: G-5

Quarter corner common to Sections 7 and 8, T.4S., R.29E., W.M.  
 The township was subdivided by Sanderson under contract 417 in 1881.  
 His record states:  
 Set sandstone 12x8x8 ins marked 1/4 on w face.  
 From which:  
 A Pine 8 in dia bears S65°E, 103 lks dist marked 1/4 SBT.  
 A Pine 24 in dia bears S75°W, 70 lks dist marked 1/4 SBT.

1	DIAGRAM	1
1	T4S R29E	1
1	1	1
1	1	1
1	1	1
1	4	1
1	S7 . S8	1
1	1996	1
1	PLS 852	1
1		1

Description of corner evidence found:

Found a stone of record size with no visible chisel marks in a stone mound. From which:  
 A Ponderosa Pine bears S65°E, 103 links with open scribe showing 1/4 S.  
 A Ponderosa Pine stump bears S75°W, 70 links with no visible scribe and a BLM bearing tree tag.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the original stone, I set a 30" x 2.25" Aluminum pipe with a 2.5" Aluminum cap 26" in the ground stamped as shown in the diagram above. I built a mound of stone around the monument.

Marked the following witness trees:

A 16" Ponderosa Pine bears N40°21'E, 29.24' scribed 1/4S8BT.  
 A 13" Ponderosa Pine bears S87°36"W, 13.57' scribed 1/4S7BT.  
 A 18" Ponderosa Pine bears N23°49'W, 42.81' scribed 1/4S7BT.

The distances and bearings are measured to the head of a nail attaching a brass washer stamped ORLS852 and WALSI3922 between the letters B and T on each tree.

This work was done October 22, 1996.

**REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR**

*David L. Haddock*

**OREGON  
 JULY 12, 1968  
 DAVID L. HADDOCK  
 852**

Office of OREGON, I hereby certify that the within instrument was filed in this office for record on the 18th day of NOVEMBER, 1996.  
 County of MORROW  
SKB by \_\_\_\_\_ (DEPUTY )  
 ( COUNTY OFFICIAL )