

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-23

**DIAGRAM**

T4S	R29E
C 1/4 S 13	
1981	
PLS 848	

History of original corner establishment:  
Corner not previously established.

Description of corner evidence found:  
N/A

Description of monument and accessories established to perpetuate the original location of this corner:  
Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram, set 24 inches in the ground.

From which  
A fir 14 inches dia. bears 572°W, 7.4 ft. scribed C 1/4 S 13 BT.  
A tamarack 10 inches dia. bears 580°E, 40.9 ft. scribed C 1/4 S 13 BT.  
Set steel posts with warning and boundary signs 5 ft. East and 5 ft. West from corner  
Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.  
Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described, on 9/10/81.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848

Witnesses:  
Mike Woodward  
Jeff Smith

Office of..... Co. Surveyor..... Umatilla.....  
State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the 7<sup>th</sup> day of January..... 1982  
by David Wilson (COUNTY OFFICIAL) by Billy Shedd (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Morrow County Surveyor

Date January 7, 1982