

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Edward W. Sanderson under Contract No. 417.

Surveyor General Records State:

Set a basalt stone 18x7x6 ins. 12 ins. in ground for 1/4 sec. cor. marked 1/4 on W. face. Raised mound of stone alongside.

No trees within limits.

No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

Found basalt stone 16"x6"x3" set in mound of stone and marked 1/4.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the corner point: Set 2 1/2"x30" galvanized iron pipe 20" in the ground with a brass cap marked as shown. From which I scribe NEW BEARING TREES:

A 48" pine bears N. 75° E. 326.0 ft. mkd. T4S R29E 1/4 S 23 BT.

A 26" pine bears S. 8° W. 206.3 ft. mkd. T4S R29E 1/4 S 22 BT.

I Nailed a brass washer marked "OPLS 598" to the BT blaze of both trees. Set a steel fence post 5 ft. South of corner. Buried original corner stone East and alongside pipe surrounded pipe with mound of stone. Used compass with 20° E. variation and steel tape, measuring to center of BTs.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. Baggett*

OREGON  
JULY 12, 1968  
ROBERT D. BAGGETT  
598

*Sept 30, 1976*

Office of..... County Surveyor..... County of..... Morrow  
State of..... Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by ..... (DEPUTY)  
(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

