


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-10

History of original corner establishment: Corner established in 1975 by Duane I. Griffith as follows: In corner position I set a 2½"x30" iron pipe with brass cap 20" into ground. Raised mound of stone 5 ft. at base to top of pipe, from which:

- A 14" tamarack bears N47°E, 50.8 ft.
- A 20" fir bears S66°E, 39.4 ft. Both scribed "CW 1/16 S33 BT" and have a brass washer nailed to BT blaze.



Description of corner evidence found: I found the brass capped iron pipe partly ripped from the ground by logging activities. The brass cap is stamped as shown in the above diagram, in addition to "1975 PLS 644". I found the above two trees alive and vigorous with scribing visible on partly healed blazes. A brass washer is nailed flush on both bearing trees.

Description of monument and accessories I established to perpetuate the original location of this corner: By reference to the bearing trees and the stone mound, which is nearly intact, I reset the brass capped iron pipe in its original position.

From which bears:

A 15" western larch with scribes visible on a partly healed blaze bears N43½°E, 50.2 ft.

A 22" white fir with scribes visible on a partly healed blaze bears S66°E, 39.4 ft.

I rebuilt the mound of stones around the iron pipe.

Compass Declination: 20° East

I hereby certify the above corner location was perpetuated as hereon described on July 24, 1984.

Witnesses: David Haddock
Steven Gaylord

Dennis L. Gaylord

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON
JULY 14, 1976
DENNIS L. GAYLORD
1698

County surveyor County of MORROW

Office of..... Oregon..... I hereby certify that the within instrument was filed in this office for record on the..... day of..... 19.....

..... by (DEPUTY) RECLIVAL BY

(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

Morrow County Surveyor

Date 8/8/84

Filed by MCD

No. 675-K

090-798-276