

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Edward W. Sanderson under contract no. 417.

Surveyor General Record States:

Set sandstone 15x8x6 ins. 10 ins. in ground for corner to secs. 2, 3, 34 and 35 marked with 2 notches on East and 4 notches on W. edges. From which:

- A black pine 6 in. in diam. brs. N. 20° E. 26 lks. dist. mkd. T4S R29E S35 BT.
 - A black pine 8 in. in diam. brs. N. 30° W. 27 lks. dist. mkd. T4S R29E S34 BT.
 - A black pine 6 in. in diam. brs. S. 46° W. 29 lks. dist. mkd. T5S R29E S 3 BT (destroyed in 1882 survey.)
 - A black pine 6 in. in diam. brs. S. 20° E. 21 lks. dist. mkd. T5S R29E S 2 BT (destroyed in 1882 survey.)
- No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

Found sandstone 15"x8"x6" set 6" in ground from which an original BT:

A 15" lodgepole snag bears S. 27° E. 13.9 ft. with scribing blaze facing corner stone no mks. (destroyed by Campbell in 1882.)

No evidence found of the other BTs.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the corner point: Set a 2½"x30" galvanized iron pipe 26" in the ground with brass cap marked as shown: From which I scribe NEW BEARING TREES:

- A 10" spruce bears N. 62° E. 25.8 ft. marked T4S R29E S35 BT.
- A 19" tamarack bears N. 15° W. 16.5 ft. marked T4S R29E S34 BT.

I nailed a brass washed marked "OPLS 598" to the BT blaze of both trees. Set a steel fence post 5 ft East of corner. Buried original corner stone East and alongside iron pipe. Used compass with 20° East variation and steel tape, measuring to center of all BTs.



Robert D. Baggett



Sept 30, 1976

Office of..... County Surveyor MORROW
State of..... Oregon..... County of.....
I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

(COUNTY OFFICIAL) by..... (DEPUTY)

