

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION R 26 E R 27 E <div style="display: flex; justify-content: space-between; border-top: 1px solid black; border-bottom: 1px solid black;"> 36 31 T 5 N </div> 6 T 4 N	TOWNSHIP T 5 N	RANGE R 26 E AND R 27 E	MORROW COUNTY
CORNER DESIGNATION: STANDARD CORNER		DATE 27 SEPT. 2008	(Please check one) <input type="checkbox"/> Condition Report Only <input checked="" type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input checked="" type="checkbox"/> Surveyed In <input checked="" type="checkbox"/> Referenced Out
Previous Renewals / Surveys. etc. I RECOVERED, TIED AND USED A 3 1/4" GLO BRASS CAP DATED 1915 MONUMENTING THIS CORNER LOCATION DURING A SURVEY FOR CAPATAL AGRICULTURAL PROPERTY SERVICES, INC. IN 1998.			
Monument(s) & Accessories Found: (Condition & Source) ALL EVIDENCE OF MONUMENT WAS REMOVED BY FARMING OPERATION DISCOVERED IN SEPT. 2008 DURING FIELD RESEARCH FOR A OREGON MAP PROJECT. USING GPS AND MY 1998 SURVEY I DETERMINED THE HISTORIC POSITION FOR THE REPLACEMENT OF THE MONUMENT. DUE TO THE CURRENT FARMING PRACTICE OF RIPPING DEEP I PLACED THE NEW BRASS CAP MONUMENT AND ATTACHED PIPE WITH THE CAP 30" BELOW THE SURFACE OF THE GROUND. AS I DUG THE HOLE TO ACCOMPLISH THIS A VERTICAL RUN OF RUST WAS EXPOSED AS I DUG. I BELIEVE THAT RUST WAS FROM 93 YEARS OF EROSION OF THE PIPE AND CAP THE GLO SET IN 1915.			
Monument Detail: <div style="text-align: center;"> </div>	Sketch: 	Monument Set (Procedures and Description): SET A 2 3/8" BRASS CAP ATTACHED TO A 2" GALVANIZED PIPE 30" BELOW SURFACE. RESET MISSING 1915 GLO MONUMENT FROM RECORD TIES. VERTICAL RUST FOUND WHILE DIGGING VERIFIED LOCATION OF 1915 GLO MONUMENT.	
New Accessories: 5/8" X 30 STEEL REBAR WITH PLASTIC CAP STAMPED LS 2850 BEARS S 64° 24' E 38.46" NEAR C/L OF SERVICE ROAD. STEEL "T" POST WITH LOCATION POSTER BEARS S 31° 52' E 65.16" STEEL "T" POST WITH LOCATION POSTER BEARS S 36° 30' W 69.92" 1" X 15" STEEL SHAFT BEARS S 64° 56' W 43.56" NEAR C/L OF SERVICE ROAD.			
Location & Comments: Compass Declination: NOT DETERMINED		SURVEYOR'S SEAL REGISTERED PROFESSIONAL LAND SURVEYOR OREGON JANUARY 20 1998 JUDSON L. COPPOCK 2850 RENEWAL DATE: DEC. 31, 2009	
Firm / Agency COPPOCK SURVEYING PO Box 495 HEPPNER, OR 97836		PARTY CHIEF JUDSON L. COPPOCK LS 2850	
Notes RECEIVED BY Morrow County Surveyor			
Witness Date <u>Oct 5 2008</u> Rec'd By <u>SKB</u> No. <u>2-1</u>			