

# OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION R 26 E   R 27 E <div style="display: flex; justify-content: space-between; border-top: 1px solid black; border-bottom: 1px solid black;"> <span>36   31</span> <span>T 5 N</span> </div> <div style="display: flex; justify-content: space-between; border-bottom: 1px solid black;"> <span>6</span> <span>T 4 N</span> </div>	TOWNSHIP T 5 N	RANGE R 26 E AND R 27 E	MORROW COUNTY
MORROW COUNTY		DATE 27 SEPT. 2008	
CORNER DESIGNATION:  STANDARD CORNER			
(Please check one)			
<input type="checkbox"/> Condition Report Only			
<input checked="" type="checkbox"/> Not Found			
<input type="checkbox"/> Renewed			
<input type="checkbox"/> Unrecorded			
<input checked="" type="checkbox"/> Surveyed In			
<input checked="" type="checkbox"/> Referenced Out			
Previous Renewals / Surveys. etc.			
I RECOVERED, TIED AND USED A 3 1/4" GLO BRASS CAP DATED 1915 MONUMENTING THIS CORNER LOCATION DURING A SURVEY FOR CAPATAL AGRICULTURAL PROPERTY SERVICES, INC. IN 1998.			
Monument(s) & Accessories Found: (Condition & Source) ALL EVIDENCE OF MONUMENT WAS REMOVED BY FARMING OPERATION DISCOVERED IN SEPT. 2008 DURING FIELD RESEARCH FOR A OREGON MAP PROJECT. USING GPS AND MY 1998 SURVEY I DETERMINED THE HISTORIC POSITION FOR THE REPLACEMENT OF THE MONUMENT. DUE TO THE CURRENT FARMING PRACTICE OF RIPPING DEEP I PLACED THE NEW BRASS CAP MONUMENT AND ATTACHED PIPE WITH THE CAP 30" BELOW THE SURFACE OF THE GROUND. AS I DUG THE HOLE TO ACCOMPLISH THIS A VERTICAL RUN OF RUST WAS EXPOSED AS I DUG. I BELIEVE THAT RUST WAS FROM 93 YEARS OF EROSION OF THE PIPE AND CAP THE GLO SET IN 1915.			
Monument Detail:		Sketch:	
Monument Set (Procedures and Description): SET A 2 3/8" BRASS CAP ATTACHED TO A 2" GALVANIZED PIPE 30" BELOW SURFACE. RESET MISSING 1915 GLO MONUMENT FROM RECORD TIES. VERTICAL RUST FOUND WHILE DIGGING VERIFIED LOCATION OF 1915 GLO MONUMENT.			
New Accessories: 5/8" X 30 STEEL REBAR WITH PLASTIC CAP STAMPED LS 2850 BEARS S 64° 24' E 38.46" NEAR C/L OF SERVICE ROAD. STEEL "T" POST WITH LOCATION POSTER BEARS S 31° 52' E 65.16" STEEL "T" POST WITH LOCATION POSTER BEARS S 36° 30' W 69.92" 1" X 15" STEEL SHAFT BEARS S 64° 56' W 43.56" NEAR C/L OF SERVICE ROAD.			
Location & Comments:		Compass Declination:  NOT DETERMINED	
Firm / Agency  COPPOCK SURVEYING PO Box 495 HEPPNER, OR 97836		SURVEYOR'S SEAL  REGISTERED PROFESSIONAL LAND SURVEYOR	
Party Chief  JUDSON L. COPPOCK LS 2850			
Notes  RECEIVED BY Morrow County Surveyor		OREGON JANUARY 20 1998 JUDSON L. COPPOCK 2850	
Witness  Date <u>Oct 5 2008</u> Rec'd By <u>SKB</u> No. <u>2-1</u>		RENEWAL DATE: DEC. 31, 2009	